

N. Lake Water Line Project

Exhibit A – effected area is the 6 properties outlines in purple on the attached drawing.

The current waterline is located underneath the actual road. The line is leaking and the ground is super saturated and causing multiple cave-ins. The original plan was to place the new waterline between the gas line and the stormwater, but with the cave-ins that is not a good option with the chance of damaging the gas line.

The three (3) alternatives are:

1. Stay in the road, only doing 200' instead of the original 400'
 - houses will need to be on a boil alert for the duration of the project, because lines will not be able to be flushed thoroughly each day
 - road will be tore-up all winter, cold patch will be extra
 - asphalt patch estimate \$12,000.00
 - premium stone backfill required

2. Place under sidewalk (400')
 - tear-up existing sidewalk r
 - replace sidewalk estimate \$12, 800.00

3. Place outside of the road right-of-way
 - Property easements for the six (6) effected properties
 - would need surveys and legal descriptions for each property
 - cost estimate has not been received



Basic Search ▾

Advanced Search ▾

Select

Sales

Layers

Refresh

Printing

Links

More...



Handwritten notes on the map:
- 6" water line
- gas line
- 100' d -
- water line
- side walk



200ft